Name	Description	Qty Units	Material Waste %	Waste % Qty	Qty w/ Waste
Division 4-Masonry					
Masonry					
Reference Sheets:	A-100, A-200				
Div-4					
CMU WALLS					
12" CMU Block Wall @ Ht 4'-9 1/2"	(Assumed Rebar)	645.02 SQ FT			
CMU Block	12"	726 Block(s)	0%	0.0	726.00
Block Mortar, 3000 LB Bulk Bag	377.5 Blocks/ Bag; 26.25 Mortar CU FT	21.99 Bag(s)	0%	0.0	21.99
Brick Sand	200 Blocks/Ton	3.63 Ton(s)	0%	0.0	3.63
Grout, 80 LB Bag	1.77 Blocks/ 0.6 CU FT	246.1 CU FT	0%	0.0	246.10
Rebar per OC spacing	16" Assumed, #4 Rebar	323.16 LBS	0%	0.0	323.16
8" CMU Block Wall 4'-9 1/2"	(Assumed Rebar)	87.66 SQ FT			
CMU Block	8"	99 Block(s)	0%	0.0	99.00
Block Mortar	425 Blocks/ Bag; 26.25 Mortar CU FT	2.99 Bag(s)	0%	0.0	2.99
Brick Sand	200 Blocks/Ton	0.49 Ton(s)	0%	0.0	0.49
Grout	2.55 Blocks/ 0.6 CU FT	23.29 CU FT	0%	0.0	23.29
Rebar per OC spacing	16" Assumed, #4 Rebar	43.92 LBS	0%	0.0	43.92